

OATES ASSOCIATES

**BRIDGE CONDITION REPORT
STRUCTURE NUMBER 027-0040**

FINAL REPORT

FAP ROUTE 798
SECTION 107BR-1
FORD COUNTY
P-93-064-02

ILLINOIS ROUTE 115
OVER DRAINAGE DITCH

Prepared for:

Illinois Department of Transportation
District 3
Ottawa, Illinois

Prepared by:

Oates Associates, Inc.
Eastport Business Center 1
100 Lanter Court, Suite 1
Collinsville, IL 62234
Phone: (618)345-2200
Email: oai@oatesassociates.com

Oates Project Number 22041

June 2004



Illinois Department of Transportation

Memorandum

To: John P. Kos Attn: Thomas R. Sancken
From: Ralph E. Anderson By: Todd E. Ahrens
Subject: BRIDGES AND STRUCTURES
Date: July 27, 2004

FAP Route 798
Section 107BR-1
Ford County

P-93-064-02
SN 027-0040 (Existing)

IL Route 115 over tributary of North Fork Vermilion River

We have reviewed the Bridge Condition Report (BCR) submitted with your memorandum dated June 29, 2004. The BCR recommends complete structure replacement using stage construction.

After reviewing the BCR, we have the following comments:

1. Based on the deteriorated condition, and low ratings, we agree with your recommendation of complete replacement. Stage construction appears feasible.
2. We concur with the proposed improved bridge clear width of 32'-0". Replacement structure type, length, and number and location of piers (if required) will be determined during the Type, Size, and Location (TSL) plan phase based on the results of a hydraulic analysis.
3. Please notify your District Geotechnical Engineer that new boring data will be required at this structure. Our Foundations and Soils Unit can be contacted if assistance is needed regarding the subsurface exploration requirements or if any existing boring or foundation data is desired.

Subject to the above comments, the Bridge Condition Report is approved. A TSL plan, structure report, proposed cross section and proposed plan and profile will be required for this project.

GGE/mrc2034
cc- John P. Kos/Attn: Terry McCleary

Recorded in ACCESS 8/3/04

Copy to McCleary SF 8/4/04
" Brayboy SF 8/4/04
" [unclear] [unclear]
" McCleary [unclear]

S		IS	
AUG 3 2004			
S&P ENG	TF		
ENVIRONMENT			
ESTIMATOR			
GEOMETRICS			
HYDRAULIC	X	SF	
LOCATIONS			
PLANS ENG			
SEE ME			
SEC			
CO-ORD			

TABLE OF CONTENTS

1.	GEOGRAPHICAL AND ADMINISTRATIVE DESCRIPTION	1
2.	PHYSICAL DESCRIPTION OF EXISTING STRUCTURE AND ROADWAY	2
3.	FIELD INSPECTION AND PHYSICAL EVALUATION	3
4.	SUMMARY STATEMENT AND PROPOSED SCOPE OF WORK	5

APPENDICIES

A	LOCATION MAP EXISTING BRIDGE CROSS SECTION APPROACH ROADWAY TYPICAL SECTION EXISTING PLAN AND PROFILE
B	1928 BRIDGE AND ROADWAY PLANS 1998 OVERLOAD INVESTIGATION MEMORANDUM BRIDGE INSPECTION REPORT MMIS INVENTORY
C	FIELD INSPECTION SKETCHES
D	PHOTOGRAPHS
E	COST ESTIMATE STAGE TRAFFIC CROSS SECTIONS PROPOSED BRIDGE DRAWING PROPOSED PLAN AND PROFILE

1. GEOGRAPHICAL AND ADMINISTRATIVE DESCRIPTION

The existing structure, Structure Number 027-0040, is located in Ford County, Illinois approximately 3.38 miles south of U.S. Route 24. The structure carries Illinois Route 115 (FAP Route 798) over a drainage ditch. The centerline of the existing bridge is at Station 178+88. See Exhibit A1 for a Location Map.

Illinois Route 115 carries two lanes of traffic and is designated as a Class II truck route. The traffic data is as follows:

Class	Minor Arterial (Rural)
ADT	600 (2001) 900 (2023)
ADTT	78 (2001) 117 (2023)
DHV (10% ADT)	60 (2001) 90 (2023)
Design Speed	55 mph
Posted Speed Limit	55 mph
Passenger Vehicles	76.6 %
Single Units	12.7 %
Multiple Units	10.7 %

Structure number 027-0040 was constructed in 1929 and is a single span reinforced concrete slab bridge with closed concrete abutments supported on timber piles. The structure is approximately 36'-3" feet in width. There are no expansion joints at the ends of the bridge.

From the February 20, 2003 Illinois Structure Information System Master Report, the following information is summarized:

Sufficiency Rating	66.8
HS Truck Inventory Rating	17.0 (30.6 tons)
HS Truck Operating Rating	33.2 (59.8 tons)

In 1998, this structure was investigated for load restriction posting. According to an Overload Investigation Memorandum from the Bureau of Bridges and Structures dated February 17, 1998, this bridge is rated for legal loads only due to deficiencies in condition of structural members.

Refer to Appendix B for a copy of the Bridge Inspection Report, MMIS inventory data and February 17, 1998 Overload Investigation Memorandum.

2. PHYSICAL DESCRIPTION OF EXISTING STRUCTURE AND ROADWAY

The existing superstructure is a single span reinforced concrete slab with a bituminous overlay. The bridge measures approximately 30'-3 ³/₄" from back to back of closed concrete abutments and has 30° right forward skew.

The existing deck measures approximately 32'-9" between curbs and 33'-11" between bridge rails. The overall width of the existing deck is 36'-3". The deck cross section consists of a concrete slab with a thickness varying from 17 ¹/₂" at the curb line to 21" at the centerline. The structure was constructed with a 4" concrete wearing surface and currently has a bituminous overlay. Concrete bridge rails with steel plate beam guardrail exist along each shoulder. Deck drainage originally consisted of 3" diameter formed openings along the curb line but have been replaced with 4"x12" aluminum deck drains.

The superstructure bears directly on the abutment walls. The reinforced closed concrete abutments are monolithic with the vertical cantilever wingwalls and bear on two rows of untreated timber pile. According to the original drawings, the piles are twelve-inch diameter and approximately 20 feet long. The piles are not battered.

The approach roadway consists of two 9-foot PCC lanes with 3-foot full depth widening along each shoulder and a bituminous overlay. The shoulders consist of 3-foot wide aggregate wedges with 1-foot earth shoulders. The overall width of the approach roadway is approximately 32'-0". The approach roadway typical section is shown in Exhibit A2. According to the original plans, 18-foot long bridge approach pavement exists at each end of the bridge, however, the approach pavement joint measures 23' from the back of each abutment (measured along the roadway centerline).

Steel plate beam guardrail exists along each shoulder and is attached to the concrete bridge rail. The guardrail terminates at each free end with Type 1 end sections. There are no utilities attached to the structure.

According to the 1928 plans, the roadway and bridge are located on a tangent horizontal alignment and a flat vertical grade (0.00%). A vertical curve ends 188 feet north (downstation) of the structure with has entrance and exit grades of -2.00% and +0.00% respectively and a length of 400 feet. A field entrance exists north of the northwest guardrail terminal.

3. FIELD INSPECTION AND PHYSICAL EVALUATION

3.1 General

The bridge was inspected on April 14, 2004. Field inspection sketches showing existing conditions of the deck, abutments and wingwalls are shown in Appendix C. Site photographs of existing conditions are shown in Appendix D.

3.2 Superstructure

The Illinois Structure Information System Master Report rates the deck and superstructure at 4 – “Poor Condition – Advanced Deterioration”.

3.2.1 Deck

The deck surface could not be inspected due to the bituminous overly and its condition could not be assessed. The overlay is in fair condition with slight rutting of the wheel lanes and some cracking. The deck drains are open and clear.

The underdeck is in poor condition. The surface is moist with efflorescence and rust stains, stalactites, tight map cracking and spalling with exposed reinforcement. Most of the spalling is isolated along the sides of the deck and around the deck drains. Efflorescence staining with stalactites occurs throughout the underdeck, which indicates the entire deck is saturated with salts.

3.2.2 Bridge Railing

The concrete bridge rail is in fair to poor condition with spalling at the base and near the ends. There is no sign of impact damage along the rail. The railing configuration and transition between the bridge railing and the steel plate beam guardrail does not meet current standards.

3.3 Approach Roadway

The approach roadway is in fair condition. Reflective cracks in the bituminous surface are forming in the pavement. Slight rutting is occurring in the wheel lanes along the overlay. The reflective cracks have been recently sealed. Bituminous patching/filling along the south abutment indicates the approach pavement is failing.

3.4 Abutments and Wingwalls

The Illinois Structure Information System Master Report rates the substructure 5 – “Fair Condition – Minor Section Loss, Cracks”.

The abutment walls are in fair to poor condition with areas of map cracking, horizontal cracks with efflorescence, spalling at the wingwall corners and hollow areas near the top of the walls. Both abutment walls have significant moisture and efflorescence staining along the front face due to leaking of the top joint. The wingwalls are in fair condition with some cracks with efflorescence, spalling and a few hollow areas.

3.5 Waterway / General Hydraulics

The Illinois Structure Information System Master Report rates the waterway adequacy as 8 - "Equal to Present Desirable Criteria" and the channel and protection as 5 - "Fair Condition – Minor Section Loss, Cracks". The structure was analyzed for scour on March 28, 1995 and the Master Report rates scour as 5 – "Stable for Scour".

The structure is on a 30° right forward skew and is slightly misaligned with the channel. The creek flows from west to east and enters the structure at an approximately 25° skew, resulting in erosion near the northwest and southeast corners of the structure. The channel is well defined and is confined by moderately sloped banks. The banks appear stable with good vegetation cover.

A preliminary hydraulic report on this structure was completed in June 2004. The report states that the existing structure does not meet clearance and freeboard requirements. No clearance exists for the 50-year high water elevation and the superstructure is partially submerged at the 100-year high water elevation. A replacement structure with a 20' channel bottom, 2:1 side slopes and a 25° skew was analyzed in the report. The report states that the proposed structure provides a larger available opening area, does not increase the water surface profiles over the existing conditions and there is no history of detrimental flooding upstream of the structure.

4. SUMMARY STATEMENT AND PROPOSED SCOPE OF WORK

4.1 Summary

The superstructure is in poor condition. Significant spalls with exposed reinforcement exist near each fascia and around drains. Efflorescence staining with stalactites exist throughout the underdeck.

The substructure is in poor condition with efflorescence staining and cracking throughout, and spalling with hollow areas near the wingwall intersections.

The approach roadway is in fair condition with reflective cracking and some rutting of the wheel lanes. The guardrail end sections and bridge railing do not meet current standards.

The waterway and general hydraulics do not meet clearance and freeboard requirements. The existing opening provides no clearance above the 50-year high water elevation. The structure has a 30° skew and the creek approaches the structure at a 25° skew.

4.2 Recommendations

Because of the poor condition of the underdeck, the superstructure is in obvious disrepair. The abutments could be rehabilitated, but areas of partial repair would be large and its long term effectiveness would be questionable. It is recommended that the existing bridge be replaced with a new structure for the following reasons:

- The amount of estimated full depth repair exceeds the maximum allowed for deck rehabilitation. Replacement of the deck is required.
- The structure was constructed in 1929 and has not had significant rehabilitation work during its life. Significant repairs would be necessary to rehabilitate the substructure. Reuse of 75-year old bridge elements is not recommended.
- The existing structure is slightly misaligned with the creek and has no clearance above the design high water elevation. The replacement structure would have more efficient hydraulics.

Therefore, the superstructure and substructure would be completely removed and replaced. The new structure would consist of a 1'-3" thick (minimum) reinforced concrete deck superstructure supported on solid concrete piers and integral abutments with a 25° right forward skew. The bridge width face to face of Type F barriers would be 32'-0" (Figure 49-3I of the BDE Manual) and 35'-2" out to out of deck. New abutments would be located outside the existing abutments resulting in a bridge length of approximately 72'-0". The channel underneath the structure would consist of a 20-foot flat bottom with 2:1 side

slopes. The channel banks beneath the bridge will be protected with riprap. The proposed bridge drawing is shown in Exhibit E.

The total estimated construction cost for replacement is \$612,000.

Raising the profile grade to provide a minimum of two feet of clearance above the high water elevation was considered (Figure 39-6A of the BDE Manual), however, this would result in significant roadway reconstruction. Therefore, it is proposed to maintain the existing profile grade across the structure, resulting in one foot of clearance above the design high water elevation. A request for a design exception would be required with this recommendation.

Bridge approach pavement will be constructed at each end of the bridge. All existing guardrail will be removed and re-erected. New traffic barrier terminals will be installed at the bridge parapet ends and at the guardrail ends, Type 6 and Type 1 (Special), respectively.

Staged construction is feasible but is subject to further evaluation during the preliminary engineering phase. Traffic control costs, time of construction and road user benefits may be the deciding factor when choosing an alternate. Economics should be evaluated considering the additional construction time and costs associated with stage construction versus closing the road and detouring traffic. Staged construction cross sections are shown in Appendix E.

4.3 Structural Investigation

The IDOT "Bridge Condition Report Procedures and Practices" states all structural elements recommended for reuse must be evaluated to determine if they can safely carry a HS20 loading under current design specifications. Since complete structure replacement is recommended (see 4.2 Recommendations), a structural investigation was not conducted.

APPENDIX A


LOCATION MAP

EXISTING BRIDGE CROSS SECTION

APPROACH ROADWAY TYPICAL SECTION

EXISTING PLAN AND PROFILE

LOCATION MAP



SN 027 - 0040
IL 115 OVER
DRAINAGE DITCH

3.4 MILES SOUTH OF US 24
IL 115 OVER DRAINAGE DITCH




OATES ASSOCIATES

ILLINOIS ROUTE 115
OVER UNNAMED STREAM
S.N. 027-0040

EXHIBIT

A1




EXISTING BRIDGE CROSS SECTION



ILLINOIS ROUTE 115
 OVER DRAINAGE DITCH
 S.N. 027-0040

EXHIBIT

A2





APPROACH ROADWAY
TYPICAL SECTION



ILLINOIS ROUTE 115
OVER DRAINAGE DITCH
S.N. 027-0040

EXHIBIT

A3



EXHIBIT

A4

APPENDIX B

1928 BRIDGE AND ROADWAY PLANS

1998 OVERLOAD INVESTIGATION MEMORANDUM

BRIDGE INSPECTION REPORT

MMIS INVENTORY

DATE	COUNTY	SEC.	INT.	FILE
10-1-19	Ford	107	105	105
Sta. 105+00	to Sta. 105+00			


SEC. 22 T26N-R9E-3rd PM.

JACOB WAGNER EST.

DAVID CLARK

20" WALKWAY


20" WALKWAY



SEC. 21 T26N-R9E-3rd PM.

MRS. GEORGE HENRY
MRS. GEORGE DAY

DANIEL KEWLEY



SEC. 22


SEC. 27 T26N-R9E-3rd PM.

MRS. MARY SHUNK

RI STA. 170+00
L = 180' 12"
Δ = 0° 15'
T = 500'
S = 0.0125'


USE 800 FT TANGENT CURVE

Construct Bridge Approach
Standard 20' - 24' open
at each end of bridge.
Set 27' 11 1/2" from Roadway Edge.



SEC. 28 T26N-R9E-3rd PM.

GUSTAVE BRAUMAN




ROUTE 226, SECTION 34

COUNTY	11F
FILE	11F
DATE	10/25/00
BY	10/25/00

SEC 34 - T26N-R9E-340 PM

JOHN WAGNER EST




JOHN WAGNER EST

SEC 34 - T26N-R9E-340 PM

JOHN BROWN


JOHN BROWN





EDWARD BORK

SEC 33 - T26N-R9E-340 PM

JOHN BROWN






STATE OF ILLINOIS
DEPARTMENT OF PUBLIC WORKS AND BUILDINGS
DIVISION OF HIGHWAYS
PLANS FOR PROPOSED
STATE BOND ISSUE HIGHWAY

INDEX OF SHEETS

Sheet No.	Title
1	Cover Sheet
2	Typical Sections
3	Summary of Quantities
4	Standard 2298-1
5	Standard 2299-1
6	Standard 2300
7	Standard 2306-1
8	Standard 2317

SCALE IN FEET
PLAN 1" = 100' PROFILE VERT. 1" = 10' CROSS SECTIONS 1" = 10'

SBI ROUTE 115
SECTION (107,108) RS-2
FORD COUNTY



- Overlay No. 17
Log Mile 9.20 to Log Mile 9.40
- Overlay No. 16
Log Mile 8.71 to Log Mile 8.77
- Overlay No. 15
Log Mile 8.45 to Log Mile 8.55
- Overlay No. 14
Log Mile 8.05 to Log Mile 8.27
- Overlay No. 13
Log Mile 7.00 to Log Mile 7.08
- Overlay No. 12
Log Mile 5.74 to Log Mile 5.92
- Overlay No. 11
Log Mile 5.60 to Log Mile 5.62
- Overlay No. 10
Log Mile 4.85 to Log Mile 5.05
- Overlay No. 9
Log Mile 4.70 to Log Mile 4.75
- Overlay No. 8
Log Mile 4.45 to Log Mile 4.56
- Overlay No. 7
Log Mile 4.29 to Log Mile 4.39
- Overlay No. 6
Log Mile 3.99 to Log Mile 4.10
- Overlay No. 5
Log Mile 3.74 to Log Mile 3.90
- Overlay No. 4
Log Mile 2.86 to Log Mile 3.05
- Overlay No. 3
Log Mile 2.45 to Log Mile 2.60
- Overlay No. 2
Log Mile 2.23 to Log Mile 2.30
- Overlay No. 1
Log Mile 1.24 to Log Mile 1.34
- Overlay No. 10
- RR Crossing
Log Mile 0.04
- Intersection S. R. 1, 115 & US 54
Begin Log Mile 0.00

GROSS LENGTH OF IMPROVEMENT - 10.15 MILES
NET LENGTH OF IMPROVEMENT - 2.26 MILES

SCALE 1 INCH = 1 MILE

CONTRACT NO. 26830

PROJECT NO.	SECTION	COUNTY	DATE	BY
115	RS-2	FORD	8	1

M-93-975-00




LOCATION OF SECTION INDICATED THUS: - - - - -

1970 ADT 550-H

STATE OF ILLINOIS
DEPARTMENT OF PUBLIC WORKS AND BUILDINGS
DIVISION OF HIGHWAYS


DESIGNED BY: *[Signature]*
CHECKED BY: *[Signature]*
IN CHARGE: *[Signature]*
DATE: *[Signature]*

PROJECT NO.	111
DATE	4-15-70
BY	W. J. [illegible]
CHECKED BY	[illegible]
APPROVED BY	[illegible]



AGGREGATE SHOULDER TYPE B IN TONS/INCH
VARY THICKNESS AS REQUIRED TO CORRECT SLOPE


TYPICAL SECTION OVERLAYS
NET TO SCALE



Q. 11 11 11 11



Q. 11 11 11 11



STATE OF TEXAS
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
DATE OF DRAWING

DATE: 4-15-70
DESIGNED BY: [illegible]
CHECKED BY: [illegible]
APPROVED BY: [illegible]
[illegible]
[illegible]

These sections are for use in the design of road shoulders. They are not to be used for construction purposes. The design of road shoulders should be based on the design of the road and the design of the shoulder. The design of the shoulder should be based on the design of the road and the design of the shoulder.



Illinois Department of Transportation

Memorandum

To: Joseph S. Hill Attn: Stan Paulis
From: Ralph E. Anderson By: Todd E. Ahrens
Subject: OVERLOAD INVESTIGATION
Date: February 17, 1998

IL Route 115
Section 107-B
Ford County
Illinois Route 115 over Drainage Ditch

SN 027-0039 & 0040

The Inventory and Rating Engineer for the Bureau of Bridges and Structures recommends the following loading restriction for this structure:

- ☐ Gross Weight _____ Pounds
☐ Single Vehicle _____ Pounds
☐ Combination Vehicle, 3 or 4 Axles _____ Pounds
☐ Combination Vehicle, 5 or More Axles _____ Pounds
☒ Legal Loads Only. This information will be entered in Roadway Referencing System.
☐ Other, Specify _____

This action has been determined for the following reason:

- ☐ Updated analysis of the structure for load-carry capacity.
☐ Impact or other damage sustained by bridge.
☒ Deficiencies in condition of structural members.
☐ Other, Specify _____

This restriction is to be observed for the following period: until the structure is rehabilitated or replaced.

GPP/RJC/bb14198
cc- James J. Jereb/Attn: Chris McCarter

Todd E. Ahrens

DISTRICT 3 BUREAU OF OPERATIONS	
FEB 19 1998	
OPERATIONS ENGR	
SERV & DEVEL ENGR	
FIELD ENGRS	
BRIDGE MAINT ENGR	
TRUCK & TR ENGR	
DESIGN & PLAN ENGR	
PERMITS	
ALLOCATION	
RECORDS	

SUFFICIENCY RATING

44.4

66.8



Illinois Department
of Transportation

Bridge Inspection Report

Sheet 1 of 4

Mo. Day Yr. Temp. Inspector

3	7	01	35'	RAY, KEENER
1	7	02	31	FANCHER, HEURICH
9	25	02	70	MCCARTER

027 - 0040

ILL 115 ; 3.38 M S OF US 24

over DRAIN DITCH

Spans = 1

Built 1929

Year

01 02 02

Remarks

Deck

Element Rating

108A Wearing Surface Type

G

108B Type of Membrane

F

108C Deck Protection

J

108D Total Deck Thickness

23"

Wearing Surface

Deck Structural Condition

Curbs

Median

Sidewalks

Parapet

Railing

Drains

Light Standards

Expansion Joints

4	3	3		
2	2	2		
2	2	-		
		-		
		-		
2	2	2		
3	3	3		
		-		
		-		

OVERLAY '99

CONC. ROTTEN AT BOTTOM

MEAS Opening

58 Condition Rating

5 5 4

'02 EXPOSED REBAR AT WATERTABLES & AT DRAINS - 1/2" OF DICK SOFFIT - AS CRACKING & LEAKING W/ STAIRS

Bridge Railing Appraisal

36 Condition Rating

3 3 3 2

3 3 3 2

3 3 3 2

TY 72

NO ET 2000

Superstructure

Bearing Devices

Stringers

Girders or Beams

Diaphragms or Braces

Crack Leaching

Joints (Leakage or Cond.)

59C Util.

Trusses

Portals and Bracing

Drainage System

Paint

Color: Facia Inter Rail

Rivets or Bolts

Weld Cracking

Rust

Timber (Decay, Damage)

Concrete Cracking

Collision Damage

LL Deflec & Vibration

Alignment of Members

		-		
		-		
		-		
		-		
2	2	2		
2	2	2		
N	-	-		
	-	-		
	-	-		
2	2	-		
	-	-		
	-	-		
	-	-		
2	2	2		
4	4	-		
4	4	4		
	-	-		

CONC. ROTTEN AROUND DRAIN W/ EXPOSED REBAR

59A MO/YR: 59B Code: 1 2 3 H

Worst % Loss %

ALONG SOFFIT W/ EXPOSED REBAR

59 Condition Rating

5 5 4

02 SAME AS DEC 01

BM-BIR-1 (Rev. 1/90)

Sheet 3 of 4

01	01	02		
----	----	----	--	--

Bridge No. 027-0040

71 Appraisal Rating

7	3	8		
---	---	---	--	--

72 Appraisal Rating

8	8	8		
---	---	---	--	--

72 A Condition Rating

Riding Quality

Settlement

Structural Condition

Relief Joints

7	6	4		
4	2	2		
3	2	2		
3	3	3		
		-		

RAMPED S - 20464

Posting

Year

□ □ □ □ □

70A2 Inspectors Rating

--	--	--	--	--

70B2 Inspectors Rating

--	--	--	--	--

70C2 Inspectors Rating

--	--	--	--	--

70D2 Inspectors Rating

☐ ☐ ☐ ☐ ☐

70A2 = Single Unit Vehicle

70B2 = Combination Type 3S- 1, 3 or 4 axles

70C2 = Combination Type 3S- 2, 5 or more axles

70D2 = One Truck at a Time

Repair
Code

Repair Description

Asgd to
Code

Priority
Code

Quantity

Unit
CostDate
Cmpl

AGENCY CODES:

TS - DISTRICT TEAM SECTION
BC - DISTRICT BRIDGE CREW
DL - DAY LABOR
MC - MAINTENANCE CONTRACT
RC - REPAIR FOR REHAB CONTRACT

PRIORITY CODES:

1 - DO THIS YEAR
2 - SHOULD DO THIS YEAR
3 - WHEN CONVENIENT

Bridge Inspection Report

Sheet 4 of 4

Year

01	22		
----	----	--	--

Bridge No. 027- 0040

Additional Remarks

'01 - DECK SOFFIT & AROUND DRAINS ROTTEN W/ EXPOSED REBAR
WINGWALLS CRACKED / ROTTEN AT CORNERS
ABUT. BACKWALL CRACKED W/ HEAVY LEACHING.

'02 NO CHANGE (S. APPR- ASPHALT "RAMP" - ROUGH)

'02 DECK & SUBF. LOWERED TO 4. EXPOSED REBAR AT EAST & WEST WATER ANGLES
AND AT DECK DRAINS. $\pm \frac{1}{2}$ OF DECK SOFFIT IS CRACKING & LEACHING WITH
STAINBLENDS. SPALL W/ EXPOSED REBAR AT W. END OF S. ABUT. CRACKING &
LEACHING AT BOTH ABUTMENTS. REBAR CAN JUST BE SEEN AT TOP

Bridge Inspection Report

Sheet 2 of 4

Bridge No. _____

Year

01 02

Substructure

Element Rating

Remarks

Abutments-Wing

3 3 3

Backwall

2 2 -

Bearing Seat

- 2 -

Stem

- 2 -

Slopes

- - -

Erosion

3 3 3

Settlement

4 4 -

Piers or Bents

- - -

Cap

- - -

Column

- - -

Crash Walls

- - -

Scour

- - -

Settlement

- - -

Fender Systems

- - -

Steel Corrosion

- - -

Timber Decay, etc.

- - -

Debris on Seat

- - -

Paint

- - -

Collision Damage

60 Condition Rating

5 5 5

CRACKS - ROTTEN AT CORNERS
CRACKS W/ LEACHING

Channel & Channel Protection

Scour of Channel

2+ 2+ 2

Erosion of Banks

2 2 2

Drift

2+ 2+ 2

Vegetation

2 2 2

Change in Channel

2 2 2

Spur Dykes & Jetties

- - -

Rip Rap or Slope Wall

61 Condition Rating

5 5 5

02 DIAPHR DAM JUST EAST OF STE.

Pier & Abutment Protection

111 Condition Rating

N N N

Culverts

Wing Walls

- - -

Head Walls

- - -

Top Slab

- - -

Walls

- - -

Floor

- - -

Siltation

- - -

Settlement

- - -

Scour

62 Condition Rating

N N N

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS STRUCTURE INFORMATION SYSTEM
MASTER REPORT
INVENTORY DATA

DATE: 02/20/2003

PAGE: 1 OF 2

STRUCTURE NUMBER: 027 - 0040 DIST: 3

FACILITY CARRIED: ILL 115
FEATURE CROSSED: DRAIN DITCH
BRIDGE REMARKS:
BRIDGE STATUS: OPEN - NO RESTRICT
STATUS REMARKS:
MAINT COUNTY: FORD
MAINT RESPONSIBILITY: I.D.O.T.
SERVICE ON/UNDER: HIGHWAY

MAINT TOWNSHIP: BRENTON

/ WATERWAY

BRIDGE NAME:
LOCATION: 3.38 M S OF US 24
BRIDGE STATUS DATE: 04 / 1988SUFFICIENCY RATING: 066.8
HBRRP ELIGIBLE: YES
REPLACED BY: 000 - 0000
REPLACES: 000 - 0000
LAST UPDATE DATE: 09/27/2002
PARALLEL STRUCTURE: NONE
MULTI-LEVEL STRUC NUMBER:
SKEW DIR: RIGHT
SKEW ANGLE: 25 00 00
STRUCTURE FLARED: NO
HISTORICAL SIGNIFICANCE: NO
BORDER BRIDGE STATE:
BDR STATE SN:
BDR STATE % RESPONSIBILITY: 00
STRUCTURAL STEEL WT: 000000000REPORTING AGENCY: I.D.O.T. - BUREAU OF MAINTENANCE
MAIN SPAN MAT"L/TYPE: CONCRETE / SLAB
NUMBER OF SPANS: (MAIN SPANS) - 01 (APPROACH SPANS) - 00

*** APPROACHES ***

NEAR #1 MAT"L/TYPE: /

NEAR #2 MAT"L/TYPE: /

FAR #1 MAT"L/TYPE: /

FAR #2 MAT"L/TYPE: /

MEDIAN WIDTH/TYPE: 00 FT. NONE

RATED BY: IDOT

RATING METHOD: ALLOWABLE STRESS

GUARDRAILS L/R: STEEL PLATE BEAM STEEL PLATE BEAM

INVENTORY RATING: HS 17.0

(231) RATING DATE: 05/11/2000

TOLL FACILITY: NO TOLL

OPERATING RATING: HS 33.2

(260)

LATITUDE: 40 D 41 M 58.69 S LONGITUDE: 88 D 10 M 50.64 S

DESIGN LOAD: 12-T ROLLER

STRUCTURE LENGTH: 30.5 SIDEWALKS UNDER STRUCTURE: NONE

AASHTO BRIDGE LENGTH: 52.3 SIDEWALK WIDTH RIGHT: 0.0

CULVERT FILL DEPTH: 0.0

*** RAILROAD CROSSING INFO ***

LENGTH OF LONG SPAN: 29.5 SIDEWALK WIDTH LEFT: 0.0

CULVERT CELLS (COUNT): 0

CROSSING 1 NBR:

BRIDGE ROADWAY WIDTH: 32.8 NAVIGATION CONTROL: NO

CULVERT OPENING AREA: 0.0

CROSSING 2 NBR:

APPR ROADWAY WIDTH: 30.0 NAVIGATION HORZ CLEAR: 0000

CULVERT CELL HEIGHT: 0.00

RR LATERAL UNDERCLEAR: 0.0

DECK WIDTH: 36.4 NAVIGATION VERT CLEAR: 000

CULVERT CELL WIDTH: 0.00

RR VERT UNDERCLEAR: 00 FT 00 IN

DECK STRUCTURE TYPE: CIP CON NRMLLY FORM DECK STRUCTURE THICKNESS: 17.5

* * * KEY ROUTE ON DATA * * *

KEY ROUTE NBR: FEDERAL-AID PRIMARY 0798 STATION: 3.38
APPURTENANCES: MAIN ROUTE 0.000 SEGMENT:
INVENTORY COUNTY: FORD LINKED: YES
TOWNSHIP/ROAD DIST: BRENTON
MUNICIPALITY:
URBAN AREA:FUNCTIONAL CLASS: MINOR ARTERIAL (RURAL) NATIONAL HWY SYSTEM: NOT ON
** CLEARANCES ** SOUTH/EAST NORTH/WEST INVENTORY DIRECTION: SOUTH
MAX. RDWY WIDTH: 32.8 FT ADT YR/COUNT: 2001 / 000600
HORIZONTAL: 32.8 FT 0.0 FT TRUCK PERCENTAGE: 13
MIN VERTICAL: 99 FT 11 IN 00 FT 00 IN NUMBER OF LANES: 02
10 FT VERTICAL: 99 FT 11 IN 00 FT 00 IN ONE OR TWO WAY: TWO-WAY
LATERAL: BYPASS LENGTH: 02
FUTURE ADT YR/COUNT: 2023 / 900
DESIGNATED TRUCK ROUTE: CLASS 2
SPECIAL SYSTEMS: NO

* * * KEY ROUTE UNDER DATA * * *

STATION: 0.00
0.000 SEGMENT:
LINKED:NATIONAL HWY SYSTEM:
INVENTORY DIRECTION:
ADT YR/COUNT: 0000 / 000000
0.0 FT 0.0 FT TRUCK PERCENTAGE: 0
0.0 FT 0.0 FT NUMBER OF LANES: 00
00 FT 00 IN 00 FT 00 IN ONE OR TWO WAY:
00 FT 00 IN 00 FT 00 IN BYPASS LENGTH: 00
0.0 FT 0.0 FT FUTURE ADT YR/COUNT: 0000 / 000
DESIGNATED TRUCK ROUTE:
SPECIAL SYSTEMS: NO

*** MARKED ROUTE ON DATA ***

DESIGNATION KIND NUMBER
ROUTE #1 MAINLINE STATE HIGHWAY 0115
ROUTE #2
ROUTE #3

*** MARKED ROUTE UNDER DATA ***

DESIGNATION KIND NUMBER

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS STRUCTURE INFORMATION SYSTEM
MASTER REPORT

DATE: 02/20/2003
PAGE: 2 OF 2

STRUCTURE NUMBER: 027 - 0040 DIST: 3

INSPECTION/IMPROVEMENT DATA

*** DATA RELATED TO INSPECTION INFORMATION ***

*** INSPECTION INTERVALS ***

ROUTINE NBIS: 12 MOS UNDERWATER: 00 MOS
FRACTURE CRITICAL: 00 MOS SPECIAL: 00 MOS

*** MAXIMUM ALLOWABLE POSTING LIMITS ***

ONE TRUCK AT A TIME: COMBINATION TYPE 3S-1: TONS
SINGLE UNIT VEHICLES: TONS COMBINATION TYPE 3S-2: TONS
BRIDGE POSTING LEVEL: LEGAL LOAD ONLY

*** INSPECTION / APPRAISAL INFORMATION ***

*** ACTUAL POSTED LIMITS ***

INSPECTION DATE 09/25/2002 SPECIAL INSPECTION DATE: 00/00/0000
INSPECTION TEMPERATURE: +70 DEG. F.
DECK: 4 POOR CONDITION - ADVANCED DETERIORATION
BRIDGE RAILING APPRAISAL: 3 MEETS STANDARDS
APPROACH GUARDRAIL: 3 3 2 ACCEPTABLE ACCEPTABLE NOT ACCEPTABLE
SUPERSTRUCTURE: 4 POOR CONDITION - ADVANCED DETERIORATION
SUBSTRUCTURE: 5 FAIR CONDITION - MINOR SECTION LOSS, CRACKS
CHANNEL AND PROTECTION: 5 FAIR CONDITION - MINOR SECTION LOSS, CRACKS
CULVERT: N NOT APPLICABLE
STRUCTURAL EVALUATION: 4 MINIMUM ADEQUACY TO BE LEFT IN PLACE
DECK GEOMETRY: 6 EQUAL TO PRESENT MINIMUM CRITERIA
UNDERCLEARANCE-VERT, LAT: N NOT APPLICABLE
WATERWAY ADEQUACY: 8 EQUAL TO PRESENT DESIRABLE CRITERIA
APPROACH RDWY ALIGN: 8 EQUAL TO PRESENT DESIRABLE CRITERIA
PIER NAVIG PROTECTION: N N/A
INSPECTED BY (NAME): McCarter

SINGLE UNIT VEHICLES: TONS
COMBINATION TYPE 3S-1: TONS
COMBINATION TYPE 3S-2: TONS
POSTED ONE TRUCK AT A TIME:

UTILITIES ATTACHED:

DECK WEARING SURFACE: BITUMINOUS OVERLAY
DECK MEMBRANE: NONE
DECK PROTECTION: NONE
TOTAL DECK THICKNESS: 23.0 IN

LAST PAINT DATE 00/0000 LAST PAINT TYPE

INSPECTION REMARKS: '02 Deck and super lowered to 4. Exposed rebar at east and west watertables and at deck drains. +- 1/2 of deck soffit is cracking and leaching w/ stalagmites. Spall w/ exp rebar @ W. end of S. abut. Beaver dam just E. of str.

*** UNDERWATER INSPECTION / APPRAISAL INFORMATION ***

INSPECTION DATE: 00/00/0000 INSPECTION CATEGORY:
TEMPERATURE: +0 F. INSPECTION METHOD:
INSPECTED BY: APPRAISAL RATING:
INSPECTION REMARKS:

*** SCOUR CRITICAL INFORMATION ***

APPRAISAL RATING: 5 STABLE FOR SCOUR EVALUATION METHOD: COMPUTER CALCULATION
ANALYSIS DATE: 03/28/1995 ANALYSIS BY (NAME): MCCARTER

***** MISCELLANEOUS *****

FRAC CRIT: NO INSP. DATE: / / APPR:
MICROFILM: YES

*** CONSTRUCTION INFORMATION ***

YEAR: 1929 ORIGINAL 0000 RECONSTRUCTED
ROUTE: SBI-115 STA: 178+88 STA:
SECTION NBR: 107-B
CONTRACT NBR:
FED AID PR #: 00000000000000
BUILT BY: I.D.O.T.

*** WATERWAY INFORMATION ***

FLOOD DESIGN FREQUENCY: 000 YRS DRAINAGE AREA: 00000000.0 ACRE
FLOOD DESIGN Q (CFS): 0000000
FLOOD DESIGN NAT H W E: 0.00 FLOOD BASE Q (C F S): 0000000
FLOOD DES OPEN PROP: 0000000 SF FLOOD BASE NAT H W E: 0.00

*** PROPOSED IMPROVEMENTS ***

*** COSTS IN DOLLARS ***


COST ESTIMATE YEAR: 0000 LENGTH: 000000
TYPE OF WORK: BRIDGE IMPROVEMENT COST: \$ 0
ROADWAY IMPROVEMENT COST: \$ 0
TOTAL PROJECT COST: \$ 0
DONE BY:
REMARKS:

APPENDIX C

FIELD INSPECTION SKETCHES

STATE OF ILLINOIS
DEPARTMENT OF PUBLIC WORKS & BUILDINGS
DIVISION OF HIGHWAYS


BOND ISSUE ROUTE NO.	COUNTY	SEC.	TOTAL SHEETS	SHEET NO.	Sheet No. 3 of 3 Sheets
115	Ford	107B	28	27	




SPECIAL ASSIGNED - J.M. Romine
CHECKED - J. J. Johnson
EXAMINED - J. J. Johnson
DESIGNED - J. J. Johnson
APPROVED - J. J. Johnson
CHIEF HIGHWAY ENGINEER


10 Ton Untr. Piling.
12" Butt. 8" Tip, 64 Req'd.
Est. Length 1280 Lin. Ft.
12 Ton Untr. Piling.
12" Butt. 8" Tip, 16 Req'd.
Est. Length 320 Lin. Ft.


S.B.I. RTE. 115 SEC. 107B
FORD COUNTY
STATION 178+88





BOTTOM OF DECK
 $\frac{1}{4}" = 1' - 0"$

 OATES ASSOCIATES	ILLINOIS ROUTE 115 OVER DRAINAGE DITCH S.N. 027-0040	EXHIBIT C2
---	--	----------------------



NORTH ABUTMENT AND WINGWALL ELEVATIONS

$\frac{1}{4}'' = 1'-0''$

LEGEND


- CRACKING
- ++ CRACKING W/ EFFLORESCENCE
- MOISTURE AND EFFLORESCENCE STAINING
- SPALLING
- HOLLOW AREAS



ILLINOIS ROUTE 115
OVER DRAINAGE DITCH
S.N. 027-0040

EXHIBIT

C3



SOUTH ABUTMENT AND WINGWALL ELEVATIONS

$\frac{1}{4}'' = 1' - 0''$

LEGEND

- CRACKING
- +++ CRACKING W/ EFFLORESCENCE
- MOISTURE AND EFFLORESCENCE STAINING
- SPALLING
- HOLLOW AREAS



ILLINOIS ROUTE 115
OVER DRAINAGE DITCH
S.N. 027-0040

EXHIBIT

C4

APPENDIX D

PHOTOGRAPHS



STRUCTURE NUMBER STAMP



UPSTREAM (taken from structure)



DOWNSTREAM (taken from structure)



LOOKING SOUTH FROM SOUTH ABUTMENT

EXHIBIT D2



LOOKING SOUTH, 30' NORTH OF NORTH ABUTMENT



LOOKING NORTH FROM NORTH ABUTMENT

EXHIBIT D3



LOOKING NORTH, 30' SOUTH OF SOUTH ABUTMENT



BRIDGE ELEVATION – UPSTREAM SIDE

EXHIBIT D4



BRIDGE ELEVATION – DOWNSTREAM SIDE



N.W. QUAD DITCH



N.E. QUAD DITCH



S.E. QUAD DITCH

EXHIBIT D6



S.W. QUAD DITCH



N.W. CORNER OF STRUCTURE (taken from flowline)



N.E. CORNER OF STRUCTURE (taken from flowline)



S.E. CORNER OF STRUCTURE (taken from flowline)

EXHIBIT D8



S.W. CORNER OF STRUCTURE (taken from flowline)



NORTH EXPANSION JOINT (looking west)

EXHIBIT D9



NORTH EXPANSION JOINT (looking east)



SOUTH EXPANSION JOINT (looking west)



SOUTH EXPANSION JOINT (looking east)



DECK SURFACE (overall) LOOKING SOUTHWEST

EXHIBIT D11



DECK SURFACE (overall) LOOKING NORTHEAST



SOUTH APPROACH PAVEMENT



SOUTH APPROACH PAVEMENT PATCH



NORTH APPROACH PAVEMENT



NORTH END OF EAST BRIDGE RAIL



SOUTH END OF EAST BRIDGE RAIL



NORTH END OF WEST BRIDGE RAIL



SOUTH END OF WEST BRIDGE RAIL



TYPICAL DECK DRAIN



WEST FASCIA

EXHIBIT D16



EAST FASCIA



TYPICAL GUARDRAIL & TERMINAL END (looking north)




SOUTH ABUTMENT (west section) (1 of 3)




SOUTH ABUTMENT (center section) (2 of 3)

EXHIBIT D18



SOUTH ABUTMENT (east section) (3 of 3)



NORTH ABUTMENT (west section) (1 of 3)



NORTH ABUTMENT (center section) (2 of 3)



NORTH ABUTMENT (east section) (3 of 3)

EXHIBIT D20



UNDERDECK (south end) (looking east)



UNDERDECK (north end) (looking east)

EXHIBIT D21



UNDERDECK (south end) (looking west)




UNDERDECK (north end) (looking west)

EXHIBIT D22



SPALLING AT NORTHEAST WINGWALL AND FASCIA



TYPICAL SPALLING AROUND DECK DRAINS

EXHIBIT D23



TYPICAL WEEP HOLE



TYPICAL SPALL AND MAP CRACKING WITH
EFFLORESCENCE IN UNDERDECK

EXHIBIT D24



SPALL ON WEST FASCIA AND UNDERDECK



SPALL ON SOUTH EAST WINGWALL / ABUTMENT

EXHIBIT D25



SPALL AND HOLLOW AREA ON NORTHEAST WINGWALL

EXHIBIT D26

APPENDIX E

COST ESTIMATE

STAGE TRAFFIC CROSS SECTIONS

PROPOSED BRIDGE DRAWING

PROPOSED PLAN AND PROFILE

**COST ESTIMATE
STRUCTURE REPLACEMENT
STRUCTURE NO. 027-0040**

ITEM	UNIT	QUANTITY	UNIT COST	COST
TRAFFIC CONTROL	L SUM	1	\$50,000	\$50,000
TEMPORARY CONCRETE BARRIER	FOOT	250	\$15	\$3,750
RELOCATE TEMPORARY BARRIER	FOOT	250	\$5	\$1,250
TEMPORARY SHEET PILING	SQ FT	1024	\$20	\$20,480
SUPERSTRUCTURE CONCRETE REMOVAL	CU YD	97	\$200	\$19,400
SUBSTRUCTURE CONCRETE REMOVAL	CU YD	111	\$300	\$33,300
PAVEMENT REMOVAL	SQ YD	907	\$15	\$13,605
REMOVE AND REERECT SPBGR	FOOT	400	\$15	\$6,000
SPBGR TERMINAL SECTION TYPE I (SPECIAL)	EACH	4	\$3,500	\$14,000
SPBGR TERMINAL SECTION TYPE 6	EACH	4	\$1,800	\$7,200
CONCRETE APPROACH PAVEMENT	SQ YD	217	\$200	\$43,400
PCC CONNECTOR PAVEMENT	SQ YD	27	\$100	\$2,700
STONE RIPRAP	SQ YD	640	\$35	\$22,400
TEMPORARY BITUMINOUS WIDENING	SQ YD	614	\$35	\$21,490
AGGREGATE SHOULDERS	SQ YD	333	\$10	\$3,330
STRUCTURE COST *	SQ FT	2532	\$130	\$329,160
EMBANKMENT RESHAPING/GRADING	L SUM	1	\$20,000	\$20,000
TOTAL REPLACEMENT COST				\$611,465


* STRUCTURE AREA = 72' X 35.17' = 2532 S.F.




ILLINOIS ROUTE 115
OVER UNNAMED STREAM
S.N. 027-0040

EXHIBIT

E1



STAGE I



STAGE II


STAGE TRAFFIC CROSS SECTIONS



ILLINOIS ROUTE 115
OVER DRAINAGE DITCH
S.N. 027-0040

EXHIBIT


E2



PROPOSED BRIDGE DRAWING

STRUCTURE DATA

TYPE: STREAM CROSSING
 NUMBER OF SPANS: 3
 APPROXIMATE LENGTH: 72'-0"
 ABUTMENT TYPE: INTEGRAL
 PIER TYPE: SOLID
 SKEW: 25°
 HORIZONTAL CURVE: NONE
 SUPERELEVATION: NONE
 VARIABLE WIDTH: NONE



CROSS SECTION

NOTE: THE ABUTMENT AND PIER LOCATIONS, DECK THICKNESS AND PROFILE GRADE ARE SUBJECT TO REFINEMENT IN THE TS&L STAGE.



ILLINOIS ROUTE 115
 OVER DRAINAGE DITCH
 S.N. 027-0040

EXHIBIT
 E3

